#8

ESTIMATE

Mota Contracting LLC
5051 Valdez Ct
Pahrump, NV 89060-1356

motacontractingllc@gmail.com
+1 (702) 672-1876

Mota
Contracting LLC

Bill to
Town Of Amargosa Valley
1640 E Amargosa Farm RD
Amargosa Valley, NV 89020 US

Ship to
Town Of Amargosa Valley
1640 E Amargosa Farm RD
Amargosa Valley, NV 89020 US

Estimate details
Estimate no.: 169
Estimate date: 11/07/2026

#	Product or service	Description	Qty	Rate	Amount
1.	**Bathroom Remodel**	Bathroom Remodel at Amargosa Park inlcudes: - Labor, materials and equipment - Remove and haul away existing plywood on walls in both bathrooms (aproximately 450 square feet) - Remove and haul away existing cabinets with sink in both bathrooms - Remove existing bathroom dividers, toilets etc - Repair any damaged plumbing and electrical in the walls - No Insulation - Clean any mold on framing and Spray Kilz on framing - Install new 3/4 Plywood and paint - Install existing bathroom dividers, toilets etc - Install new 36" cabinet with drop in sink in both bathrooms Clean up work area	1	$6,700.00	$6,700.00
2.	**Epoxy Flooring**	Epoxy Flooring (325 squarefeet) at Amargosa Park includes:	1	$1,850.00	$1,850.00

- Labor and materials

- Etch and Clean concrete floor

- Pressure wash floor

- Install Epoxy flooring with color chips

Clean work area

Total **$8,550.00**

Note to customer

Job duration at approximately 4 to 5 business days.

If weather applies we will notify owner and keep communication.

We ask 50% down to commence work.

Final payment when finish and approved by Contractor/Home Owner.

Estimate valid for 30 days from above date.

Accepted date **Accepted by**